



Steve Heiner Photos

## Canyon Project Nears Halfway Mark

A Utah Department of Transportation project of widening 800 North in Orem and constructing a interchange with a overpass and a new bridge over the Provo River (above) at the mouth of Provo Canyon is 41 percent complete, said Ernest J. Wilson, UDOT District Six construction engineer.

The project started in February and is set for an August, 1985, completion date.

The \$6.1 million project includes swinging an overpass over North University Avenue for traffic turning towards Heber City off

800 North in Orem.

The widening of 800 North between State Street and 600 East is also part of the same project. That phase of the project includes widening to two, 12-foot lanes of traffic going each direction, installing a 13-foot turn lane in the middle. Curb and gutter on each side is also included.

The 800 North widening project is to be completed within the next two months, Wilson said.

3 Aug 1984